

A. GENERAL:

1. To repair cooling towers at Hall B: BAC: #15296-2, 15250-2 located at the Anaheim Convention Center.
2. Warrant all parts and labor for a minimum of one year.

B. COOLING TOWER FILL REPLACEMENT:

1. Remove and dispose of off-site all inlet air louvers, fill media & supports.
2. Replace with OEM inlet air louvers hanging fill sheets and support.
3. Block style fill media will not be accepted, BAC fill material parBYRK1012MG.

C. COAT INTERIOR WET SURFACES AS LISTED WITH CLMLOOO:

1. Sandblast all listed areas to NACE standard #3
 - A) Cold water basin
 - B) Interior and bottom of new hot water basins
 - C) Interior galvanized supports
 - D) All accessible side walls in cold basin area
2. Apply CIM 1000 Primer
3. Apply CIM 1000 to all prepared surfaces

D. REPLACE HOT WATER DISTRIBUTION BOXES:

1. Demo & remove existing hot water basins including pre-distribution assembly
2. Provide and install new water distribution nozzles
3. All material to be OEM
4. Clean up and dispose of all material off-site

E. REPLACE OUTLET SCREENS:

1. Remove existing outlet screen and replace with stainless steel outlet screen