



City of Anaheim

DEPARTMENT OF PUBLIC WORKS

From: Department of Public Works

Date: January 17, 2012

RE: Lincoln Avenue Median Island Improvements
From 275' E/O Knott Avenue to Knott Avenue
RCP2012-09235

FOR INFORMATION ONLY, the Department of Public Works is advertising for bids to construct Median Island Improvements on Lincoln Avenue from 275' E/O Knott Avenue to Knott Avenue. The work to be performed under this contract generally consists of median concrete curb, striping and asphalt concrete pavement resurfacing. The work, to be undertaken, consists of removing existing improvements, mainly A.C. pavement and sub-grade areas. After which, backfilling, compacting sub-grade, median concrete curb, and surrounding A.C. pavement will be constructed. The work includes removal and reconstruction of handicap access ramps, curb and gutter. Existing striping will be removed through sandblasting and new traffic striping and pavement markings and signs will be installed and appurtenant work thereto necessary for the proper construction of proposed improvements, in accordance with Plans and Specifications.

Note: Suggested License Classification - "A" – General Engineering Contractor

10% bid bond required.

Liquidated Damages will be \$1,500 per day.

ADVERTISEMENT DATES: 1/26/12, 2/02/12 & 2/09/12
BID DATE: 2/16/12 BID TIME: 2:00 PM
CITY ESTIMATE: \$67,368.00
WORKING DAYS: 30 Days
PROJECT MANAGER: CESAR CARILLO (714.765.5176)

The bid documents (including plans and specifications) are available from C2 Reprographics by clicking the link below or by visiting www.C2repro.com and entering the Public Plan Room and selecting the project name. If you pre-order sets, hard copies are available at C2 Reprographics, 4051 E. La Palma, Suite F, Anaheim, Ca 92807. For assistance, please contact: Brian Ehler at planwell@c2repro.com, (866) 632-8329. The project plan holders list including "plan rooms" is also available at C2repro.com. No refunds will be made for returned plans and specifications.

https://order.planwell.com/x_project.asp?de=5f1cf9f6-3483-40ee-b60b-08caa527eac9

H:\PROJECT FOLDERS-ACTIVE\Lincoln Ave-Median Island Improvements\Notice of Bid\NOTICE TO BID-LINCOLN AVE.docx
DM/Cc: Clerical (5) Contract Administration

PROPOSAL

For the construction of
LINCOLN AVENUE – MEDIAN ISLAND
 FROM 275' E/O KNOTT AVE. TO KNOTT AVE.

Anaheim, California
 Adv. Dates: 1/26/12, 2/02/12
 & 2/09/12

Bid Dates: 2/16/12
 Bid Times: 2:00 P.M.

	Item Description	Bid Quantity	Unit Price	Total
1	Unclassified Excavation.	146 CY	\$	\$
2	Asphalt Concrete.	142 TON	\$	\$
3	Remove Exist. Traffic Signal Pull Boxes.	1 LS	\$	\$
4	Remove Exist. Curb Ramp, Curb, Curb & Gutter, and Sidewalk. Reconstruct PCC Access Ramp Per APWA Std. 111-3, with Detectable Warning Device (3'x 4' Truncated Dome). Case A, Type 3, Section B-B, Detail D.	1 EA	\$	\$
5	Construct 0.67'(8") PCC Type "D" Median Curb per COA Std. 120 and Median Taper 140-2.	471 LF	\$	\$
6	Median Backfill with Compacted Subgrade Preparation and Fine Grading.	47 CY	\$	\$
7	Median Backfill with new topsoil & plant new 5-gallon shrubs, modify exist. Irrigation System and remove exist. topsoil & exist. shrubs in landscaping area.	1 LS	\$	\$
8	Construct 0.34'(4") Min. thick Stamped Concrete with Basketweave Pattern (Match Exist. Color) Per COA Std. 143.	1,050 SF	\$	\$
9	Furnish and Install Construction Information Sign.	2 EA	\$	\$
10	Remove and Replace Traffic Loops Type "E" Circular Per COA Std. 410.	8 EA	\$	\$
11	Remove Conflicting Striping by wet sandblasting and markers from Sta.10+64 to 15+10 prior to installation new striping and markers.	1 LS	\$	\$
12	Install 4" Broken White Lane Line with Type A & G Raised Pavement Markers Per COA Std. 451-E.	650 LF	\$	\$
13	Install 4" Solid White Lane Line with Type A, G & C Raised Pavement Markers Per COA Std. 459.	100 LF	\$	\$
14	Install 8" Solid White Lane Line with Type A, G & C Raised Pavement Markers Per COA Std. 452-B.	300 LF	\$	\$
15	Install 12" Solid White Stop Bar Per COA Std. 435-C (Thermoplastic).	100 LF	\$	\$

