



City of Anaheim
Fire Department
Fire Prevention Bureau



Specifications and Requirements

Subject: ASBESTOS REMOVAL

References: California Fire Code, 2001 Edition, Section 8707

Permit Requirements

A permit is required from the Anaheim Fire Department's Fire Prevention Division to remove asbestos except for the removal of asbestos from:

- 1) Pumps, valves, gaskets and similar equipment
- 2) Pipes, ducts, girders or beams, which have a length of less than 21 linear feet.
- 3) Wall or ceiling panels which have an area of less than 10 square feet or a dimension of less than 10 linear feet.
- 4) Floor tiles when the duration of work can be completed in less than four hours.

Notification

The dispatch center must be notified 24 hours prior to commencement and closure of asbestos removal operations. The phone number is (714) 533-1305.

The permit applicant must notify the City of Anaheim Building Division when asbestos abatement involves the removal of materials, which were used as a feature of the building's fire resistance.

Conditions of Removal

Plastic film, which is installed on building elements during asbestos removal, shall be flame resistant.

Signs shall be posted at the entrance, exit and exit access door, decontamination areas and waste disposal areas. The signs shall state that:

- ◆ Asbestos is being removed from the area.
- ◆ Asbestos is a suspected carcinogen.
- ◆ Proper respiratory protection is required.

Signs shall have a reflective surface and lettering shall be a minimum of two inches in height.

For further information regarding these requirements contact: Fire Prevention Bureau at (714) 765-4040 between the hours of 8:00 a.m. to 5:00 p.m., Monday through Friday.