


SCOPE: THIS STANDARD SHOWS REQUIRED VAULT NECK ASSEMBLY, MANHOLE COVER AND NECK EXTENSIONS FOR TRAFFIC INSTALLATIONS.



NOTES:

- A. ALL ITEMS SHALL MEET AASHTO-20 TRAFFIC RATING.
- B. NECK ASSEMBLY SHALL CONSIST OF VAULT NECK, COVER AND MANHOLE COVER.
- C. MANHOLE COVER AND FRAME SHALL HAVE 30" DIA. CLEAR OPENING.
- D. MANHOLE COVER SHALL BE FURNISHED WITH: BOLTS, "T" STYLE GASKET AND PICK HOLE PLUG.
- E. ONE NECK EXTENSION IS REQUIRED. ORDER ADDITIONAL NECK EXTENSIONS WITH REQUIRED HEIGHT AS NEEDED.
 6" EXTENSION SECTION, WT. 877 LBS.
 9" EXTENSION SECTION, WT. 1,316 LBS.
 12" EXTENSION SECTION, WT. 1,755 LBS.
- F. VAULT LADDER SHALL BE FURNISHED WITH THIS INSTALLATION.
- G. SEE CONSTRUCTION STANDARDS CU 1600-3F, -3H, -95, -95A, -95B, -33, 34 FOR VAULTS REQUIRING THIS NECK ASSEMBLY AND EXTENSIONS.
- H. LADDER MAY BE POSITIONED IN DIFFERENT ORIENTATION AS SPACE REQUIRES. PROVIDE LADDER HOOKUPS ON FOUR QUADRANTS.
- I. DO NOT INTERCHANGE MANUFACTURERS. FOR JENSEN VAULTS, ORDER JENSEN PART NO. K45-VN12-16T.

FILENAME: CU1600-3C REV6

<p>CITY OF ANAHEIM PUBLIC UTILITIES DEPARTMENT ELECTRICAL DIVISION T&D CONSTRUCTION STANDARDS</p>		REVISION KEYS:	ADDED / REVISED TEXT	ADDED / REVISED MATERIAL	NEW SHEET
		VAULT NECK AND COVER DETAILS			
					ISSUE DATE: 01-08
					SHEET 1 OF 1
					CONSTRUCTION STANDARD:
					CU 1600-3C
APPROVALS					
T&D MGR	FIELD MGR	OPER. MGR			