


PARKWAYS

- A. FACE OF CURB TO \odot OF TREE - 3' MIN.
 B. STREET LIGHT
 10' MIN. FOR PALM
 15' MIN. FOR ALL OTHERS
 C. DRIVEWAY FROM TOP OF X OR B.C.R. - 10' MIN.



- D. UTILITIES AND SIGNS
 FIREHYDRANT 5' MIN.
 CATCH BASIN 5' MIN.
 SEWER LATERAL 10' MIN.
 ROADWAY SIGN 10' MIN.

MEDIANS

- A. FACE OF CURB TO \odot OF TREE - 5' MIN.
 B. END OF MEDIAN OR BEGINNING OF LEFT
 TURN LANE - 40' MIN.



- C. STREET LIGHT
 10' MIN. FOR PALM
 15' MIN. FOR ALL OTHERS
 D. UTILITIES AND SIGNS
 WATER MAIN 5' MIN.
 STORM DRAIN 5' MIN.
 SEWER MAIN
 AND LATERAL 10' MIN.
 ROADWAY SIGN 10' MIN.

REC'D <i>[Signature]</i>	8/21/03	APP <i>[Signature]</i>	8/29/03	A	9/18/03	
DEPUTY CITY ENGINEER	DATE	D.P.W. / CITY ENGINEER	DATE	REVISED	BY	

CITY OF ANAHEIM DEPARTMENT OF PUBLIC WORKS

PARKWAY AND MEDIAN ISLAND TREE PLANTING CLEARANCE

STANDARD DETAIL NO.

530-A

USE WITH STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION

SHEET 1 OF 2

INTERSECTIONS

A. SIGNALIZED


APPROACH 25' MIN. FOR PALM FROM B.C.R.
40' MIN. FOR ALL OTHERS FROM B.C.R.

DEPARTURE 15' MIN. FOR PALM FROM E.C.R.
25' MIN. FOR ALL OTHERS FROM E.C.R.

B. STOP SIGN OR UNCONTROLLED

APPROACH 25' MIN. FROM B.C.R.

DEPARTURE 10' MIN. FROM E.C.R.



REC'D	<i>[Signature]</i>	8/21/03	APP	<i>[Signature]</i>	8/29/03	A	9/18/03
	DEPUTY CITY ENGINEER	DATE		D.P.W. CITY ENGINEER	DATE		REVISED
							BY

CITY OF ANAHEIM DEPARTMENT OF PUBLIC WORKS

PARKWAY AND MEDIAN ISLAND TREE PLANTING CLEARANCE

STANDARD DETAIL NO.

530-A

USE WITH STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION

SHEET 2 OF 2